



भारतीय प्रौद्योगिकी संस्थान रोपड़
INDIAN INSTITUTE OF TECHNOLOGY ROPAR
नंगल रोड, रूपनगर, पंजाब-140001/Nangal Road, Rupnagar, Punjab-140001
Ph. 01881-242193, e-mail: purchase@iitrpr.ac.in

No.IITRPR/EE/2011/10

Date: 08/11/2011

NOTICE INVITING QUOTATION

Sealed item rate quotations are invited from enlisted contractors of CPWD/ PB PWD B&R/ PUDA for the following works on prescribed Performa.

| S.No | Name of Work | Estimated Amount |
|------|--|------------------|
| 1 | Providing Cement Concrete flooring in power system & core lab. | Rs.49,500/- |

1. The quotations should reach the Office of Executive Engineer on or before 21.11.2011 upto 3:00 PM & shall be opened on the same day at 3:30 PM in the presence of contractors or their representatives, who may like to be present.
2. The Director IIT Ropar reserves the right to cancel any or all the quotations without assigning any reason.
3. The work should be executed strictly as per CPWD specifications/ BOQ.
4. Conditional quotation shall be rejected.
5. Completion time within 20 days from the award of work.
6. The quotation shall be valid for 30 days.
7. Payment shall be made on the basis of actual measurement.

Executive Engineer
IIT, Ropar

Endst. No. _____ Dated. _____

BOQ FOR P/L CEMENT CONCRETE FLOORING IN POWER SYSTEM AND CORE LAB. (R.No-124)
AT TRANSIT CAMPUS OF IIT ROPAR

| S.NO. | DESCRIPTION OF ITEMS | QTY | UNIT | RATE in fig. | RATE in words | AMOUNT |
|-------|---|-----|------|-----------------|------------------|--------|
| 1 | Providing and fixing glass strips in joints of terrazo/ cement concrete floors. 40 mm wide and 4 mm thick. | 198 | Rmt | | | |
| 2 | Cement concrete flooring 1:2:4 (1 cement: 2 coarse sand : 4 graded stone aggregate) finished with a floating coat of neat cement including cement slurry, but excluding the cost of nosing of steps etc. Approved quality Plasticizer is mixed @200ml per 50 kg of cement or as per manufactures specifications. Complete as per directions of E-I-C. 40mm thick with 6 to 10 mm nominal size stone aggregate. | 165 | sqm | | | |
| | Total | | | | | |

(Signature of contractor with seal)